

CITY CONTRACTS
REFERENCE FOR OTHERS

TEMPORARY EROSION &
SEDIMENT CONTROL MEASURES
(T.E.S.C.M.)

GENERAL NOTES:

1. THE SOIL RETENTION INSTALLATION DETAILS SHOWN FOR CULVERT PROTECTION SHALL BE USED FOR ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES UTILIZING SOIL RETENTION BLANKETS UNLESS OTHERWISE NOTED.
2. ROCK PLACEMENT USED IN THE TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHOWN ON THESE SHEETS SHALL HAVE A MINIMUM THICKNESS OF 6 INCHES UNLESS OTHERWISE INDICATED.
3. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES PLACED WITHIN THE CONSTRUCTION CLEAR ZONE SHALL BE INSTALLED WITH 8:1 SLOPES PARALLEL TO TRAFFIC AND 4:1 SLOPES PERPENDICULAR TO TRAFFIC.
4. SEDIMENT TRAPS SHALL BE CLEANED OF ACCUMULATED SEDIMENT WHEN APPROXIMATELY 50% FILLED.
5. CHECK DAMS SHALL BE CLEANED OF ACCUMULATED SEDIMENT WHEN THE DEPOSITS REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE CHECK DAM.
6. CULVERT PROTECTIONS SHALL BE INSTALLED UPON INITIATION OF EARTH ACTIVITIES AND MAINTAINED AS MUCH AS PRACTICAL UNTIL STABILIZATION IS COMPLETED AND ACCEPTED. CULVERT PROTECTIONS MAY BE REMOVED FOR PERIODS OF TIME AS REQUIRED DURING CONSTRUCTION TO COMPLETE ADJACENT IMPROVEMENTS.
7. THE CONTRACTOR MAY CONSTRUCT AN EARTH DIKE AS SHOWN, OR RELOCATE THE CHECK DAMS AS CONSTRUCTION PROGRESSES. NO DIRECT PAYMENT SHALL BE MADE FOR RELOCATION OF THE CHECK DAMS.

NOT TO SCALE

CONSTRUCTION
STANDARDS


TEMPORARY EROSION
CONTROL LABELS

STANDARD No. D-627 SHEET 1 OF 2

CITY OF
AZTEC
PUBLIC WORKS
DEPARTMENT

CITY CONTRACTS

REFERENCE FOR OTHERS



TYPICAL USAGE OF SELECTED EROSION AND SEDIMENT CONTROL MEASURES

STANDARD SYMBOLS FOR EROSION AND SEDIMENT CONTROL MEASURES

Silt Fence		Slope Drain		Sediment Trap,	
Straw Bale		Drop Inlet Protection		Sediment Trap, Excavated	
Earth Dike (Berm)		Culvert Protection		Sediment Basin	
Diversion Channel (Swale)		Check Dam		Triangular Sediment Filter Dike	

NOT TO SCALE

CONSTRUCTION
STANDARDS

TEMPORARY EROSION NOTES

STANDARD No. D-627 SHEET 2 OF 2

CITY OF
AZTEC
PUBLIC WORKS
DEPARTMENT