

## **ADDENDUM #1**

ITB # 2025-866

## **REBID HARTMAN PARK FIELD LIGHTING**

ADDENDUM DATE: March 12, 2025

BID DUE DATE/ TIME: March 17, 2025, 3:00 PM

## This addendum includes the following:

- 1. Clarifications between engineer's documents and Geomat Report
  - A discussion point was made for the method for handling water within drilled holes. The engineers' documents initially required the holes to remain free of water and debris. However, the geotechnical report suggested an alternative approach of using a tremie method to displace water during concrete placement. If a dry hole is required, additional measures such as casing or drillers' mud would be necessary, increasing costs. Local drilling capabilities were discussed, noting that certain methods could be significantly more expensive if specialized equipment is needed.
  - The City confirmed that displacing water with a concrete pump is an
    efficient and acceptable method and to proceed with the tremie method
    for concrete placement.

For Further Information Contact: Vanessa Tanner, Procurement Manager, CPO Phone: 505-334-7652

email: vtanner@aztecnm.gov